



PROUDLY SERVING CENTRAL KENTUCKY

SINCE 1931

FARM PRODUCTS

INSTALLATION INSTRUCTIONS

AVAILABLE UPON REQUEST

Phone # (859) 623-4238

Fax # (859) 623-4255

106 Industry Road

Richmond, KY. 40475

WWW.CONCRETEMATERIALS.CO

MADE IN HOUSE BY LOCAL SKILLED WORKERS

*****All prices listed are subject to change without notice and are not guaranteed. Prices stated do not include any sales tax or delivery fees.**

FARM PRODUCTS



CATTLE GUARDS

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 5/8 INCH STEEL REBAR AND FIBER MESH
- 1-FOOT HIGH, 12 OR 16 FEET LONG, AND 8 FEET WIDE
- 10 THREE INCH GIRDERS SPACED 4 ½ INCHES AT THE TOP AND 2 1/2 INCHES AT THE BASE
- WEIGHT OF 12 FOOT GUARD IS 8,500 LBS, WEIGHT OF 16 FOOT GUARD IS 10,500 LBS
- COST FOR 12 FOOT IS \$1725.00
- COST FOR 16 FOOT IS \$2300.00

FARM PRODUCTS



350 GALLON STOCK WATER TANK (WITH A BALL FLOAT BARRIER)

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 3/8 INCH STEEL REBAR AND FIBER MESH
- 2 FEET 7 INCHES AND 6 FEET 4 INCHES IN DIAMETER
- BALL FLOAT KEEPS THE WATER TO 22 INCHES INSIDE THE TANK
- THE SLOPE OF INSIDE WALL IS DESIGNED TO PREVENT FREEZING
- TOTAL WEIGHT IS 5,150 LBS
- COST IS \$575.00

FARM PRODUCTS



8 FOOT AND 12 FOOT CATTLE FEED TROUGH

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 3/8 INCH STEEL REBAR AND FIBER MESH
- 8 FOOT CATTLE FEED TROUGH MEASUREMENTS ARE 28 INCHES TALL, 8 FEET LONG, AND 39 INCHES WIDE
- 12 FOOT CATTLE FEED TROUGH MEASUREMENTS ARE 28 INCHES TALL, 12 FEET LONG AND 39 INCHES WIDE
- MADE WITH ONE END, TWO ENDS, OR NO ENDS (8 FOOT ONLY)
- TOTAL WEIGHT OF 8 FOOT FEED TROUGH 3000 LBS
- TOTAL WEIGHT OF 12 FOOT FEED TROUGH 4000 LBS
- COST FOR 8 FOOT WITH ANY COMBINATION \$270.5
- COST FOR 12 FOOT NO ENDS \$402.50, AND FEED TROUGH ENDS \$34.50

FARM PRODUCTS



8 FOOT FENCE LINE FEED BUNK

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 3/8 INCH STEEL REBAR AND FIBER MESH
- MEASUREMENTS ARE 30 INCHES TALL (BACKSIDE) 22 INCHES (FRONTSIDE), 8 FEET LONG, AND 34 INCHES WIDE
- MADE WITH FORK LIFT POCKETS IN THE BASE TO MOVE AROUND ON THE FARM
- TOTAL WEIGHT IS 2,800 LBS
- COST IS \$258.75

FARM PRODUCTS



350 GALLON STOCK WATER TANK PAD

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH ½ INCH STEEL REBAR AND FIBER MESH
- 5 FEET LONG, 5 FEET WIDE, 4 INCHES TALL
- 18 INCH CENTER HOLE ALLOWS FOR HEATING UNIT
- TOTAL WEIGHT 450LBS
- COST IS \$259.00

STORM SHELTER/ SAFE ROOM



FAMILY STORM SHELTER/SAFE ROOM

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- 78" WIDE, 100" LONG, 56" TALL
- 6" STEEL REINFORCED LID
- REINFORCED WITH 3/8" + 5/8" STEEL REBAR AND FIBER MESH
- STEEL DOOR OPENING 24" BY 42"
- WEIGHS 10,000 LBS
- 2 FRESH AIR VENT PIPES'
- COST IS \$ 1725.00

STORM SHELTER/SAFE ROOM



FAMILY STORM SHELTER/SAFE ROOM (TORNADO TUBE)

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- 64" WIDE, 142" LONG, 80" TALL
- REINFORCED WITH ½" STEEL REBAR AND FIBER MESH
- STEEL DOOR OPENING 45" BY 26"
- WEIGHS 18,000 LBS
- COST IS \$3220.00

STORM SHELTER/SAFE ROOM



FEMA APPROVED FAMILY STORM SHELTER/SAFE ROOM (TORNADO TUBE)

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- 64" WIDE, 142" LONG, 80" TALL
- REINFORCED WITH ½" STEEL REBAR AND FIBER MESH
- STEEL DOOR OPENING 45" BY 26"
- WEIGHS 18,000 LBS
- COST IS \$4945.00