



**PROUDLY SERVING CENTRAL KENTUCKY**

**SINCE 1931**

## **FARM PRODUCTS**

**INSTALLATION INSTRUCTIONS**

**AVAILABLE UPON REQUEST**

**Phone # (859) 623-4238**

**Fax # (859) 623-4255**

**106 Industry Road**

**Richmond, KY. 40475**

**[WWW.CONCRETEMATERIALS.CO](http://WWW.CONCRETEMATERIALS.CO)**

**MADE IN HOUSE BY LOCAL SKILLED WORKERS**

**\*\*\*All prices listed are subject to change without notice and are not guaranteed. Prices stated do not include any sales tax or delivery fees.**

## FARM PRODUCTS



---

### CATTLE GUARDS

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 5/8 INCH STEEL REBAR AND FIBER MESH
- 1-FOOT HIGH, 12 OR 16 FEET LONG, AND 8 FEET WIDE
- 10 THREE INCH GIRDERS SPACED 4 ½ INCHES AT THE TOP AND 2 1/2 INCHES AT THE BASE
- WEIGHT OF 12 FOOT GUARD IS 8,500 LBS, WEIGHT OF 16 FOOT GUARD IS 10,500 LBS
- COST FOR 12 FOOT IS \$1811.00
- COST FOR 16 FOOT IS \$2415.00



## FARM PRODUCTS



---

### 350 GALLON STOCK WATER TANK (WITH A BALL FLOAT BARRIER)

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 3/8 INCH STEEL REBAR AND FIBER MESH
- 2 FEET 7 INCHES AND 6 FEET 4 INCHES IN DIAMETER
- BALL FLOAT KEEPS THE WATER TO 22 INCHES INSIDE THE TANK
- THE SLOPE OF INSIDE WALL IS DESIGNED TO PREVENT FREEZING
- TOTAL WEIGHT IS 5,150 LBS
- COST IS \$654.00

## FARM PRODUCTS



---

### 8 FOOT AND 12 FOOT CATTLE FEED TROUGH

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 3/8 INCH STEEL REBAR AND FIBER MESH
- 8 FOOT CATTLE FEED TROUGH MEASUREMENTS ARE 28 INCHES TALL, 8 FEET LONG, AND 39 INCHES WIDE
- 12 FOOT CATTLE FEED TROUGH MEASUREMENTS ARE 28 INCHES TALL, 12 FEET LONG AND 39 INCHES WIDE
- MADE WITH ONE END, TWO ENDS, OR NO ENDS (8 FOOT ONLY)
- TOTAL WEIGHT OF 8 FOOT FEED TROUGH 3000 LBS
- TOTAL WEIGHT OF 12 FOOT FEED TROUGH 4000 LBS
- COST FOR 8 FOOT WITH ANY COMBINATION \$272.00
- COST FOR 12 FOOT NO ENDS \$439.00, AND FEED TROUGH ENDS \$36.00



## FARM PRODUCTS



---

### 8 FOOT FENCE LINE FEED BUNK

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH 3/8 INCH STEEL REBAR AND FIBER MESH
- MEASUREMENTS ARE 30 INCHES TALL (BACKSIDE) 22 INCHES (FRONTSIDE), 8 FEET LONG, AND 34 INCHES WIDE
- MADE WITH FORK LIFT POCKETS IN THE BASE TO MOVE AROUND ON THE FARM
- TOTAL WEIGHT IS 2,800 LBS
- COST IS \$300.00

## FARM PRODUCTS



---

### 350 GALLON STOCK WATER TANK PAD

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- REINFORCED WITH ½ INCH STEEL REBAR AND FIBER MESH
- 5 FEET LONG, 5 FEET WIDE, 4 INCHES TALL
- 18 INCH CENTER HOLE ALLOWS FOR HEATING UNIT
- TOTAL WEIGHT 450LBS
- COST IS \$285.00



## STORM SHELTER/ SAFE ROOM



---

### FAMILY STORM SHELTER/SAFE ROOM

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- 78" WIDE, 100" LONG, 56" TALL
- 6" STEEL REINFORCED LID
- REINFORCED WITH 3/8" + 5/8" STEEL REBAR AND FIBER MESH
- STEEL DOOR OPENING 24" BY 42"
- WEIGHS 10,000 LBS
- 2 FRESH AIR VENT PIPES'
- COST IS \$ 1811.00

## **STORM SHELTER/SAFE ROOM**



---

### **FAMILY STORM SHELTER/SAFE ROOM (TORNADO TUBE)**

- **CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)**
- **64" WIDE, 142" LONG, 80" TALL**
- **REINFORCED WITH ½" STEEL REBAR AND FIBER MESH**
- **STEEL DOOR OPENING 45" BY 26"**
- **WEIGHS 18,000 LBS**
- **COST IS \$3381.00**



## STORM SHELTER/SAFE ROOM



---

### FEMA APPROVED FAMILY STORM SHELTER/SAFE ROOM (TORNADO TUBE)

- CONCRETE RATED FOR 4000 POUNDS PER SQUARE INCH (4000 PSI)
- 64" WIDE, 142" LONG, 80" TALL
- REINFORCED WITH ½" STEEL REBAR AND FIBER MESH
- STEEL DOOR OPENING 45" BY 26"
- WEIGHS 18,000 LBS
- COST IS \$5192.00